

Brenham ISD
Erate Cabling Walk Through
Q&A
12-19-2022

1. When do you want the work to commence? **This summer 2023. Prefer ear to mid July.**
2. What connector type for fiber enclosure panels? **LC (preferred) or SC**
3. What brand of keystone and panel do you want for termination in the closets? **Bids for functionally equivalent equipment will be accepted. Our district uses Panduit.**
4. Brenham Junior High School: How much clearance between drop ceiling and deck? **The main building is about 6-8". The other buildings are 2-3 feet.**
5. Brenham Junior High School: **Where are the cables to be located in the gym? Drill through the entrance hallway wall and the APs will be attached to the wall.**
6. Brenham Junior High School: How does fiber run from the main building MDF to the English building? **4" conduit is provided with innerduct to outside and then fiber lays on awning to the English building where hole is drilled to enter the English building IDF.**
7. The copper runs in your buildings, do you want them to run strictly in the halls or can we traverse rooms? **The decision is up to the contractor as long as they stay in the copper cabling ethernet specifications for length.**
8. Early Childhood Learning Center: The classrooms on the one side of the hallway have no drop ceilings. Where do you want the cable loop? **Those rooms will need to have holes drilled through the thin wall at the top and dropped in the ceiling vent shaft. The school district will handle it from there.**